



COVERED GRANDSTAND AND CHANGING FACILITIES

Construction of facilities for Newry Town Football Club

Client: Newry Town Football Club

SUMMARY:

Value: £0.5 million
Architect: MPA Architects
Contractor: G. Taylor
Status: Complete

Services Provided:
Detailed Design
Piling & Structural Steelwork
BoQ and Tender Documentation
Project Supervision

The construction of the 650 seater covered stand was completed for Newry Town (now Newry City) football club in 2003.

Unfavourable ground conditions required pre-cast driven concrete piles to support the superstructure. The 9m cantilevered roof was restrained by floor and wall loading from the accommodation provided below the pre-cast concrete terracing.

An extensive layout of changing rooms, treatment rooms, shower and toilet facilities have been built below the stand.

Pre-cast concrete terracing units supplied by Creagh Concrete were used to create the upper platform.

