



ALTO MOLOCUE - RIO LIGONHA ROAD (LOT 3) SUPERVISION

EuropeAid 119437/D/SV/M2 - Mozambique

Client: Administracao Nacional de Estradas (ANE)

SUMMARY:

Value: €1.4 million Consultancy
€27.5 million Works

Status: Completion Dec 2008

Finance: EU / EDF

Contractor: CMC, Italy / Mozambique

Services Provided:

- Construction supervision services under EDF Conditions of Contract.
- Progress monitoring, financial management, quality control and claims management.
- Final measurements of completed works and provisional and final acceptance of works.
- Maintenance obligations.

Narrative Description of Project:

- Upgrading 106 km of the National Primary Route EN1 from a deteriorated gravel road to full bitumenised road standard.
- Construction of a new bridge over the Rio Ligonha consisting of 13 spans with a river crossing length of 178 metres
- Pavement Reconstruction consists of the following:-
 - 2 No. 150mm layers of gravel selected subgrade
 - 1 No. 225mm layer of cement/lime stabilised subbase
 - 1 No. 150mm layer of mechanically modified base course
 - 2 No. layers of surface dressing seal with 19/9mm chips
 - Miscellaneous ancillary works (signage, roadmarking, culverts, drainage etc)



Nicholas O'Dwyer
CONSULTING ENGINEERS