



TULLYALLEN VILLAGE ROAD IMPROVEMENT SCHEME

Client: Louth County Council

SUMMARY:

Value: €1.0 million

Status: Complete

Services Provided:

Feasibility, Planning,
Detailed Design, Tender Process
Project Supervision and Contract Administration

The works were located along the main road through the village of Tullyallen, Co. Louth from its junction with the R168 Collon Road to its junction with King Williams Glen Road. The works area also included junctions with other local roads and other associated works, most notably at Watery Lane. The Construction Stage for the entire works was 40 weeks.

The Contract provided for the construction of the following civil works;

- Re-construction of existing junction with the R168 Collon Road.
- Overlaying existing road carriageway pavement with hot-mixed materials over a total length of 1300m.
- Overlaying and re-grading of existing road carriageway pavement at Watery Lane
- Re-construction of existing footpaths and construction of new 2m wide footpaths and dished crossings.
- Re-construction of existing drainage system and construction of new drainage and attenuation system over various lengths.
- Overlaying existing road junctions and entrances to private properties to tie-in to new pavement overlay works.
- Installation of new services ducting and public lighting ducting and lamp standards.
- Installation of new road signage and re-lining of completed road pavement.

